

## Case Study

### HOPPER DREDGER KB1649



Beens Dredging B.V.



### MEASURING TASK

Determination of sludge density behind the suction pump.

Pipe diameter:	508 mm (20 inch)
Pipe material:	Steel
Solids:	10 - 35 wt%
Density:	1 – 1.4 ton/m <sup>3</sup>
Temperature:	5°C – 25°C (41°F – 77°F)

### INSTRUMENT USED

SDM – slurry density meter. Installed in a pipe by means of a metal weld-on piece (weldolet).

### CHALLENGE

Beens Dredging got the assignment to remove a certain amount of sludge from the port in Amsterdam to ensure a safe passage for ships. The operator of the ship wants to fill the hopper with sand as quickly as possible to reduce the total time spent on this project. A density meter was needed to monitor the real-time density of the sludge.

### SOLUTION

The SDM is a good solution for this measuring task, because of its reliable, stable and real-time measurement results. The instrument uses non-nuclear technology, so there are no additional safety costs or governmental restrictions.

The density meter is used in combination with a flow meter to determine the optimal dredging condition. The density and flow rate are both shown at a (digital) cross meter in the wheelhouse. This cross meter helps the operator to execute a dredging session more efficiently, resulting in a reduction of the total project time and accordingly also the costs.

### RESULTS

The SDM contributes to:

- Determination of the optimal dredging condition
- Efficient completion of the dredging session
- Reduction of time and money spent on a project
- Quicker response to changing process conditions
- Less obstruction of the pump



### FOR FURTHER INFORMATION

Please contact Rhosonics

Phone: +31 341 – 37 00 73

Email: [info@rhosonics.nl](mailto:info@rhosonics.nl)

Website: [www.rhosonics.nl](http://www.rhosonics.nl)

Follow us on social media:



Or contact our dredging specialist STI-BV

Website: [www.sti-bv.nl](http://www.sti-bv.nl)